Duct Diversion Works for East Leeds Link Road

BT/Skanska/morrison - Project Briefing

SCD Group Limited, Radial Park, Manston Lane, Leeds LS15 8ST Tel: 0870 750 6416 Web: www.scd-ltd.com

BT/Skanska/Morrison

Duct Diversion Works for East Leeds Link Road

SCD was contracted to Skanska/Morrison on behalf of BT *openreach* to carry out major diversionary works.

This work on BT apparatus was to allow the construction of bases and formwork to carry the flyover which spans Hunslet Road, one of Leeds' main arterial roads.

The work involved the construction of man holes, footway and carriageway chambers and the laying of more than 1.6km of 2, 4, 6 and 16 way duct formations.

Project Summary

- Installation of telecommunications duct infrastructure, including:
  - ◊ 1.6km ducting to BT *openreach* specification
  - ◊ Chamber construction to BT *openreach* specification
  - ◊ Man hole construction to BT *openreach* specification
- Hard landscaping, including:
  - ◊ Tactile paving
  - ◊ Kerbing
  - ◊ Carriageway reinstatement
- Temporary pedestrian walkways, including:
  - ◊ Formation of footpaths
  - ◊ GSB type 1 stone
  - ◊ 20mm DBM base course
  - ◊ 6mm DBM wearing course