



12.7KM DUCTING AND HV CABLE INSTALLATION IN DRIFFIELD

INTERSERVE AND CE ELECTRIC - PROJECT BRIEFING

"I know we are only a small Parish and when considering a contract such as this we are not too significant. To the residents it is extremely important, and to have benefitted from the caring and courteous approach of SCD and Interserve, working in partnership with East Riding of Yorkshire Council Highways and the Parish Council has been a pleasure.."

R L Mole, Lt Colonel (retired), Clerk, Foston on the Wolds Parish Council





Interserve and CE Electric Services

12.7km Ducting and HV Cable Installation in Driffield

SCD Group Limited were contracted to provide essential enabling works for the new wind turbine farm near Driffield North Yorkshire.



The project was deemed highly sensitive to local residents who were opposed to the scheme.

SCD liaised closely with the residents and Parish Councils to alleviate concerns through attendance at Parish Council meetings and letter drops. These were supplemented by regular update meetings and emails.

SCD completed the works a full 2 weeks ahead of schedule and gained the thanks and praise of locals for the cooperative and empathetic approach taken.

Project Summary

- Installation of ducted system including:
 - ◇ 12.7km of HV approved ducting (Emtelle)
 - ◇ Underground joint bays
 - ◇ Highway and Road closure noticing
 - ◇ Traffic management diversion design and implementation
- Installation of 66Kv Cable:
 - ◇ 70km of cable installed
 - ◇ Direct buried joints
 - ◇ Cable fletted off at each of 16 turbines
- Programme:
 - ◇ 10 weeks construction and cable installation
 - ◇ On time and on budget